

# ESTIMATE



## Prepared For

Wallace Lake Estates, Steve Martin.  
Wallace Lakes Dr  
Wallace , Ca 95254  
(209) 502-4338

## All Around Asphalt

Valley Springs, Ca 95252  
Phone: (209) 348-0006  
Email: Allaroundsphalt@yahoo.com

Estimate # 206634  
Date 02/24/2026

Description	Total
-------------	-------

---

(complete package)	\$73,150.65
--------------------	-------------

Package option #01 Includes all work such as:

Power cleaning entire roadways and cracks, making sure any and all debris, weeds and contaminants are removed from asphalt surfaces and cracks.

Grinding out all major spiderwebbing areas, compacting road base, applying SS/1H adhesive to all edges of area to be patched, installing up to 3" hot asphalt compacted to CA specs.

Machine applied hot rubber crack filler to all cracks in roadways, applying sand to rubber surface to eliminate tracking and promote adhesion of asphalt sealant.

Applying Overkote asphalt sealant to entire asphalt roadways and re striping all roadway lines/dashes.

---

(Patching & Crack filling only)	\$46,150.00
---------------------------------	-------------

Power cleaning entire roadways and cracks, making sure any and all debris, weeds and contaminants are removed from asphalt surfaces and cracks.

Grinding out all major spiderwebbing areas, compacting road base, applying SS/1H adhesive to all edges of area to be patched, installing up to 3" hot asphalt compacted to CA specs.

Machine applied hot rubber crack filler to all cracks in roadways, applying sand to rubber surface to eliminate tracking.

---

(Crack filling only)	\$23,750.00
----------------------	-------------

Power cleaning entire roadways and cracks, making sure any and all debris, weeds and contaminants are removed from asphalt surfaces and cracks.

Machine applied hot rubber crack filler to all cracks in roadways, applying sand to rubber surface to eliminate tracking

---

(6 month maintenance plan)

\$11,500.00

Power cleaning entire roadways and cracks, making sure any and all debris, weeds and contaminants are removed from asphalt surfaces and cracks.

Machine applied hot rubber crack filler to all cracks in roadways, applying sand to rubber surface to eliminate tracking.

---

**Subtotal** \$154,550.65

---

**Total** **\$154,550.65**

---

**Notes:**

(DO NOT LOOK AT TOTAL AT BOTTOM OF ESTIMATE)

Pricing is listed with item.

If you select which package/option of work to be done estimate will be updated to show exact price.

All patchwork covered under one year warranty.

Time to complete entire project: 7-10 days.

Vehicle traffic to have complete access unless asphalt coating is applied. If coating is applied no vehicle access on coated areas for approximately 16-24 hours. Foot traffic is permitted within 3-6 hours.

Payments: Material deposit required within minimum of 3 business days before work scheduled to begin with balance due upon completion.

Forms of payment accepted include Cashiers Check, Wire transfer, Zelle, Venmo, Credit card and cash.

Credit card payments subject to 4% processing fee.

By signing this document, the customer agrees to the services and conditions outlined in this document.

A handwritten signature in black ink, appearing to read 'AS', with a large, stylized flourish extending to the right.

---

Signed on: 02/24/2026  
Andrew Stanley

---

Wallace Lake Estates, Steve Martin.